The Surrey County Council
Proposed Copenhagen Crossing in D6250 Laytons Lane, Sunbury On Thames

Statement of reasons

In the interest of road safety, the provision of a new continuous footway crossing arrangement is required in accordance with SCC Healthy Streets Guidance at the existing kerbed bell-mouth junction of Nursery Road and Laytons Lane. This will be a permanent change to the highway layout, so timing /restrictions are not applicable.

Description of the location and length of the restriction

The continuous footway crossing is proposed to run across the northern end of Laytons Lane at the junction with Nursery Road. The length of the proposed crossing is 8.3m (along the Nursery Road channel line) and 6.1m (at rear of the crossing in Laytons Lane), with a crossing width of 2.5m and ramp lengths of 0.8m (at 1:10 gradient)

The TRO works are required in the interest of road safety and in order to deliver works required to discharge Condition 14 of planning permission ref SP21/00258/SCC.