FACILITY TYPE

FOOTBALL AND RUGBY ONLY
NON-INFILL SYNTHETIC TURF PITCH PLAYZONE
WITH PERIMETER FENCING, FLOODLIGHTING,
HARD-STANDING AREA AND EQUIPMENT

CONSTRUCTION

40mm 3G NON-INFILL SYNTHETIC TURF
15mm PREFABRICATED SHOCKPAD
250mm SUB BASE (INC BLINDING LAYER)
FORMATION LAYER

DIMENSIONS

FENCE TO FENCE = 30 X 20m
2NR GOAL RECESSES = 3.66 X 1m
SPECTATOR AREA = 30 X 2m
ACCESS ROUTE = NEW POROUS ASPHALT PATH

LINE MARKING

GOAL BOXES = 10.0 X 5.0m
GOAL LINE = 3.66Lm
CENTRE LINE = 20Lm
CENTRE CIRCLE = 0.2M RADIUS
TRY LINE = 2NR 20Lm

PERIMETER FENCING

3m NEW TWIN BAR PANEL FENCING
1NR SINGLE GATE ACCESS
2 NR DOUBLE GATES
COLOUR RAL6005 - DARK GREEN
4m NEW FENCING OVER GOALS - WHITE
BALL STOP NETTING OVER FENCING TO
SOUTHERN END TOTAL HEIGHT OF NETTING 5m

LED FLOODLIGHTING

8.0m HIGH STAND ALONE FLOODLIGHT COLUMNS
4NR LUMINAIRES)
AVERAGE LUX = 120LUX
UNIFORMITY = 0.65
(LIGHTING PLAN SEPARATE)

STREET LIGHTING

8 NR STREET LIGHTS TO EXISTING PATHS

EQUIPMENT

2NR GOALS (INTEGRAL TO FENCING)
2NR BENCHES
2NR WASTE BINS
1NR STORAGE CONTAINER

AFTER CARE

BI-MONTHLY VISITS REQUIRED FOR DURATION
OF END OF DEFECTS PERIOD (6NR VISITS)



NOTES

- PAINTED MACADAM SURFACE
- MACADAM SPECTATOR AREA AND ACCESS
- DG DOUBLE GATE
- SG SINGLE GATE
- FL FLOODLIGHT
- SL STREET LIGHT

FOR PLAYZONE AND PATHWAY LIGHTING DETAILS REFER TO LIGHTING DESIGNS.

Rev	Amendment	Date	By
-	Initial Issue		

Client: LONDON BOROUGH HARINGEY

Project: BRUCE CASTLE PARK PLAYZONE

Drawing: PROPOSED LAYOUT PATH

McARDLE SPORT TEC

Drawn	Date	Scales	
NJM	15-07-24	1:200	
Checked	Plot No 01	Prelim	Check / Final

Job No	Drawing No	Rev
	MCA-MUK3299-02	E