THIS DRAWING IS COPYRIGHT AND MUST NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN AUTHORITY

GENERAL NOTES

1. All works to be carried out in accordance to MCHW Specification for Highway Works and Surrey County Council Standard Detail Drawings.

Site Clearance Plan Key:

- Indicates Extent of existing shrub/grass clearance.
- Indicates extent of break out existing pavement construction to construct tie-in detail.
- Indicates extent of existing footway construction to be broken out, and re-profiled incorporating new un-controlled tactile paving crossing.
- Break out existing tarmac construction and ready for new full crossover construction.
- Existing surface courses to be removed, ready for new surface courses.
- Existing corduroy Blocks to be removed and replaced with footpath construction.
- Existing road sign to be removed.
- Break out existing gully, to be located at new revised position.

Existing right turn ahead sign to be removed.

Existing right turn ahead sign to be removed.

Existing 30/40mph signs to be removed.

Existing back to back 30/40mph speed signs to be removed.

Existing continuous cycleway/footway segregation line to be burnt off back to new transition point.

Existing back to back Shared footway/cycleway signs to be removed.

Existing 40mph marking to be burnt off.

Existing 30/40mph signs to be removed.

Existing side road sign to be replaced with staggered junction sign to diag 507.1

REV	DATE	AMENDMENT	BY	CHKD

STATUS TENDER

PROJECT
Green Lane
Chertsey

CLIENT
CHARTWAY PARTNERSHIPS GROUP

DRAWING
Section 278
Site Clearance Plan

DATE 28/3/26 DRAWN BY AB
SCALES (@A1) - 1:250 CHECKED BY LW
WALKERS JOB NUMBER 8090
REVISION

DRG NO.
23-0035-WAC-ZZ-00-DR-D-3705

Walker Associates Consulting Limited
Structural and Civil Engineers
13 Capricorn Centre
Cranes Farm Road
Basildon, Essex
SS14 3JJ
01268 530 500
walker-associates.co.uk