For Final Review
NOT FOR CONSTRUCTION

Drawing Number
167879-99997-WST-MLN1-DRG-EHW-010016 A03

ST MARY'S HOSPITAL

ST MARY'S HOSPITAL
MINT WING

SOUTH WHARF ROAD

WINSLAND STREET

TANNER LANE

PADDINGTON SQUARE

PADDINGTON STATION

EXISTING LIGHTING COLUMN TO REMAIN

PROPOSED DISABLED BADGE HOLDER PARKING BAYS

PROPOSED 6m EXTENSION TO MOTORCYCLE PARKING BAY

PROPOSED DISABLED BADGE HOLDER PARKING BAY

EXISTING WALL MOUNTED LIGHT TO REMAIN

PROPOSED BOLLARDS

FOOTWAY TO BE WIDENED

PROPOSED WALL MOUNTED LIGHT

KERBS TO BE LAID FLUSH IN FOOTWAY TO TRACE EXISTING HISTORIC KERB ALIGNMENT

EXISTING WALL MOUNTED LIGHT TO REMAIN

PROPOSED WALL MOUNTED LIGHT

UNCONTROLLED PEDESTRIAN CROSSING. TACTILE PAVING SLABS IN COLOUR 'NATURAL'

UNCONTROLLED PEDESTRIAN CROSSING. TACTILE PAVING SLABS IN COLOUR 'CHARCOAL'

PROPOSED DISABLED BADGE HOLDER PARKING BAY

PROPOSED LIGHTING COLUMN

PROPOSED CYCLE STANDS

FOOTWAY TO BE WIDENED

PROPOSED LIGHTING COLUMN

NEW PAVING TO TIE INTO RECENTLY INSTALLED PAVING AND FUTURE INSTALLATION OF CYCLE HIRE BAY

AREA PEDESTRIANISED AS A RESULT OF ADJACENT HIGHWAY SCHEME

OS map data reproduced by permission of Ordnance Survey on behalf of HMSO. © Crown copyright 2025. All rights reserved. Ordnance Survey licence number 0100040692

PDF Created: 20-OCT-2025 - 15:53 - Valid only at time of creation

Legend/Notes

NOTES

1. DO NOT SCALE FROM THIS DRAWING OR THE COMPUTER DIGITAL DATA. DIMENSIONS ON THIS DRAWING ARE PROVIDED FOR INFORMATION ONLY AND SHOULD NOT BE USED FOR SETTING OUT.
2. THE DESIGN IS BASED ON TWO TOPOGRAPHICAL SURVEYS. THE FIRST WAS CARRIED OUT BY CLEAR ROUTE LTD IN DECEMBER 2021. THE SECOND WAS CARRIED OUT BY SOCOTEC IN APRIL 2025. ELEMENTS OF BOTH SURVEYS ARE USED IN THE DESIGN DUE TO ONGOING CONSTRUCTION WORK ON SITE.
3. LIGHTING DESIGN SHOWN FOR CO-ORDINATION PURPOSES. DESIGN IS BY WSP ON BEHALF OF WESTMINSTER CITY COUNCIL. FOR DETAILS OF DESIGN REFER TO DRAWING UK0029995.4264-WSP-P01-X-DR-LI-1300-01

LEGEND

- PROPOSED CARRIAGEWAY RECONSTRUCTION/RESURFACING WITH ASPHALT FINISH
- PROPOSED ASPHALT FOOTWAY
- PROPOSED ARTIFICIAL STONE PAVERS
- PROPOSED STONE PAVERS
- PROPOSED TACTILE PAVING SLABS
- PROPOSED BOLLARD
- PROPOSED CYCLE STAND
- PROPOSED SIGN POST
- PROPOSED WHITE/YELLOW ROAD MARKINGS
- PROPOSED DRAINAGE CHANNEL WITH SOLID GRATING
- PROPOSED GRANITE KERB LAID FLUSH IN FOOTWAY
- PROPOSED LIGHTING COLUMN
- PROPOSED WALL MOUNTED LIGHT
- EXISTING LIGHTING COLUMN
- EXISTING WALL MOUNTED LIGHT

0 4 8 12 16 20m

SCALE 1:200

Rev	Date	Description of Revisions	Drawn	Chkd	Appr
P03	09/10/25	ISSUED FOR PUBLIC CONSULTATION	FT	BW	CT
P04	09/10/25	ISSUED FOR PUBLIC CONSULTATION	FT	BW	CT
P05	20/10/25	ISSUED FOR PUBLIC CONSULTATION	GS	GM	CW
A03	20/10/25	ISSUED FOR PUBLIC CONSULTATION	GS	GM	CW

Status: Fit for Internal Review & Comment
Suitability: S3

Authorised | Signed | Date

Contractor(s): Arup

Location: PADDINGTON-BRISTOL-PENZANCE

Type: CAD Drawing | Sub-type

Role: Drainage and Highways Engineer General | Sub-Role

Zone: Western Region

Phasing | Project Stage: 0

Region: Wales and Western

Contract No.: 167879

Contract Title: London Street

Drawing Title: HIGHWAY DESIGN GENERAL ARRANGEMENT PUBLIC CONSULTATION DRAWING

Designed	G. Salmon	Signed	Date 17/10/25
Drawn	G.Salmon	Signed Electronically Signed	Date 17/10/25
Checked	G.Macgillivray	Signed Electronically Signed	Date 20/10/25
Approved	C.Woodman	Signed Electronically Signed	Date 20/10/25

Scale(s): 1:200 | ELR & Mileage: 0.012 to 0.012

Alternative Reference | Sheet of

Drawing Number: 167879-99997-WST-MLN1-DRG-EHW-010016 | Revision: A03

Sheet Size A1 594 x 841